




HVAC PLAN - FITNESS CENTER
 SCALE: 1/4"=1'-0"

FLEX SIZE SCHEDULE	
1-35 CFM	4"
36-59 CFM	5"
60-95 CFM	6"
101-150 CFM	7"
151-209 CFM	8"
206-280 CFM	9"
281-360 CFM	10"
361-490 CFM	11"
491-600 CFM	12"
601-900 CFM	14"
901-1250 CFM	16"
1251-1750 CFM	18"
1751-2250 CFM	20"
2251-3800 CFM	24"

MATERIALS AND WORKMANSHIP SHALL COMPLY WITH ALL APPLICABLE CODES AND ORDINANCES IN THEIR LATEST REVISIONS.

CONTRACTOR TO COORDINATE SPECIFIC REQUIREMENTS OF EQUIPMENT WITH MANUFACTURERS' SHOP DRAWINGS.

ALL EQUIPMENT SHALL BE INSTALLED STRICTLY IN ACCORDANCE WITH THE MANUFACTURERS WRITTEN INSTALLATION INSTRUCTIONS.

REVISIONS	BY

RGD & ASSOCIATES
INC.
 Consulting Engineers
 1000 Lake Park Lane, Suite 2, Jupiter, Florida 33458

CONSTRUCTION DOCUMENTS FOR:
RGD EXAMPLE PROJECT
 ANYTOWN, FLORIDA
 ANYPLACE

ROBERT DANENWORTZ P.E.
 GEORGE A. LEE P.E.
 MECHANICAL ENGINEER
 DATE

Date: DATE

Scale:

Drawn:

Checked: RGD

Job# XX-XXXX

Sheet

M-2.3
 Of Sheet